



1	Stationary (Front) Head—Channel	20	Slip-on Backing Flange
2	Stationary (Front) Head—Bonnet	21	Floating Tubesheet Skirt
3	Stationary (Front) Head Flange	22	Floating Tubesheet Skirt
4	Channel Cover	23	Packing Box Flange
5	Stationary Head Nozzle	24	Packing
6	Stationary Tubesheet	25	Packing Follower Ring
7	Tubes	26	Lantern Ring
8	Shell	27	Tie Rods and Spacers
9	Shell Cover	28	Transverse Baffles or Support Plates
10	Shell Flange—Stationary Head End	29	Impingement Baffle or Plate
11	Shell Flange—Rear Head End	30	Longitudinal Baffle
12	Shell Nozzle	31	Pass Partition
13	Shell Cover Flange	32	Vent Connection
14	Expansion Joint	33	Drain Connection
15	Floating Tubesheet	34	Instrument Connection
16	Floating Head Cover	35	Support Saddle
17	Floating Head Flange	36	Lifting Lug
18	Floating Head Backing Device	37	Support Bracket
19	Split Shear Ring		

Obtain work permit	1	22-Apr-26 11:00	22-Apr-26 12:00
Carry out blinding	6	22-Apr-26 12:00	22-Apr-26 18:00
Carry out removal of insulation	5	22-Apr-26 18:00	22-Apr-26 23:00
Disconnect inlet / outlet connection as (if) required	12	22-Apr-26 23:00	23-Apr-26 11:00
Shift crane and bundle puller at job location	2	22-Apr-26 18:00	22-Apr-26 20:00
Set up crane at job location	3	22-Apr-26 20:00	22-Apr-26 23:00
Carry out de-torquing of channel head / channel cover	7	23-Apr-26 11:00	23-Apr-26 18:00
Rig & drop channel head / channel cover / back cover	3	23-Apr-26 18:00	23-Apr-26 21:00
Modify scaffolding for tube bundle pull out	4	23-Apr-26 21:00	24-Apr-26 01:00
Prepare, Set up & align bundle puller by using crane	3	22-Apr-26 23:00	23-Apr-26 02:00
Mobilize the flat bed truck at job location.	1	23-Apr-26 02:00	23-Apr-26 03:00
Pull out tube bundle, load & secure it on trailer	5	24-Apr-26 01:00	24-Apr-26 06:00
Offer as found inspection of tube bundle	1	24-Apr-26 06:00	24-Apr-26 07:00
Shift and unload the Tube Bundle at cleaning location	1	24-Apr-26 07:00	24-Apr-26 08:00
Marked up tube for hydrojetting / ANDT as if required	4	24-Apr-26 08:00	24-Apr-26 12:00
Perform hydrojetting and air blowing of tubes	12	24-Apr-26 12:00	25-Apr-26 00:00
Offer tube cleaning inspection	2	25-Apr-26 00:00	25-Apr-26 02:00
Contingency retubing as (if) required	24	25-Apr-26 02:00	26-Apr-26 02:00
Carry out ANDT (IRIS / ECT / RFET / RVI etc.) of tube	12	26-Apr-26 02:00	26-Apr-26 14:00
Shift tube bundle at job location	1	26-Apr-26 14:00	26-Apr-26 15:00
Modify / provide scaffolding access for shell internal ins	4	24-Apr-26 06:00	24-Apr-26 10:00
Offer initial inspection of shell / channel head / channel	2	24-Apr-26 10:00	24-Apr-26 12:00

[illegible]

Drw Purpose Code :-		Statutory Note: This document is prepared by rPlan and is the sole proprietary of the company. Its purpose is educational and no references within this document are for Engineering or Design correlation with the applicable codes. For any clarifications beyond the intended purpose viewers can always correspond to rPlan via its company website. This drw is not for duplication without company permission!		Description: Typical Exchangers FRAGMENT	
Status of Approval :-		Drw electronic code		Preliminary Doc under prep	
Dimentions as Mentioned					
Drawing Scale :-		rPlan AT 39, MERMAID 1 CHS LTD., SEC-11, CBD-BELAPUR, NAVI MUMBAI - 400614		Drawn By: _____ Drawn Date _____	
Engg Code :-	Backup Info Code :-	Legal Owner		QR CODE	
Angle of Projection		Sheet Size		Checked Approved by _____ Checked Approved Date _____	
				Drawing Number _____	
				Sheet _____ Rev XX 1 of 1	