SCHEDULE QUALITY · BASELINE CHECK

The DCMA 14-Point Assessment

Validate your baseline programme before the client does

THE 14 CHECKS & THRESHOLDS

green border = zero-tolerance / hard fail

1	**Logic** — Activities missing predecessor / successor	≤ 5%	2	**Leads** — Negative lags on relationships	ZERO
3	**Lags** — Relationships carrying positive lag	≤ 5%	4	**Relationship Types** — Logic should be Finish-to-Start	≥ 90% FS
5	**Hard Constraints** — Forced dates overriding logic	≤ 5%	6	**High Float** — Total Float over 44 working days	≤ 5%
7	**Negative Float** — Plan breaking its own constraints	ZERO	8	**High Duration** — Activities longer than 44 days	≤ 5%
9	**Invalid Dates** — Actuals ahead / forecasts behind data date	ZERO	10	**Resources** — Activities loaded with resources or cost	100%
11	**Missed Tasks** — Finishing later than baseline finish	≤ 5%	12	**Critical Path Test** — Finish date must move with critical delay	PASS
13	**CPLI** — (CP length + float) ÷ CP length	≥ 0.95	14	**BEI** — Tasks completed ÷ tasks planned	≥ 0.95

Checks 2, 7, 9 & 12 are instant rejections

Leads, negative float, invalid dates or a failed critical path test will get the baseline sent back.

Source: US Defense Contract Management Agency · Run in P6 via Schedule Log (F9), filters & a critical-path stress test



Notes:
1) the original creators of DCMA 14 point assessment program were NASA where the scheduling crosschecks are based on this scheme
2) On EPCM projects, long schedules undergo process based development
3) Need for assessment of schedule sanctity and preciseness becomes essential not to create too many conflicts
4) During usage of the schedule an incorrect schedule provides conflicting problems in updates and reports
5) Above two captioned pictures included on this document are samples of scheme adoptions practiced in the industry on date

Drw Purpose Code :- 01	Statutory Note: This document is prepared by rPlan and is the sole proprietory of the company.Its purpose is educational and no references within this document are for Engineering or Design corelation with the applicable codes. For any clarifications beyond the intended purpose viewers can always correspond to rPlan via its company website.This drw is not for duplication without company permission!	Description: Schedule Quality Check DCMA 14 Point Assessment	
Status of Approval :- 01			
Dimentions as Mentioned NA	Drw electronic code	Drawn By: DFT-01	Drawn Date 20260821
Drawing Scale :- NTS	rPlan AT 39, MERMAID 1 CHS LTD., SEC-11, CBD-BELAPUR, NAVI MUMBAI - 400614	Checked Approved by rPlan-01	Checked Approved Date 20260825
Engg Code :- 01 / Backup Info Code :- 01	Legal Owner / QR CODE	Drawing Number As Barcoded	Sheet 1 of 1 / Rev 00
Angle of Projection NA / Sheet Size A3			